

Feasibility Study Cost Estimate - SUMMARY
S-2: Targeted Soil Cover with Land Use Controls
Burton Island OU2
NRG-Indian River Power

<i>Task</i>		<i>Capital Cost</i>	<i>O&M Costs</i>
Capital Costs			
Permitting		\$50,000	--
Site Preparation		\$232,978	--
Cover Placement		\$251,067	--
Restoration		\$68,616	--
Universal Environmental Covenant		\$300,000	--
Subtotal:		\$902,660	--
Contingency	15%	\$135,399	--
Project Management	8%	\$72,213	--
Total Capital Costs:		\$1,110,272	--
Annual O&M Costs			
Cover Inspection		--	\$1,290
Perimeter Patrols		--	\$29,200
Cover Repair		--	\$698
Invasives Management (first 5 years only)		--	\$15,000
Subtotal:		--	\$46,188
Contingency	15%	--	\$6,928
Project Management	8%	--	\$3,695
Total Annual O&M Costs (first 5 years)		--	\$56,811
Total Annual O&M Costs (after 5 years)		--	\$38,361
Years of Operation		--	30
Discount Rate		--	2%
Total O&M Present Worth (2012 \$)		--	\$946,119
Total Present Worth Cost (2012 \$, 30 Yrs at 2%)			\$2,056,391

Feasibility Study Cost Estimate - DETAIL
 S-2: Targeted Soil Cover with Land Use Controls
 Burton Island OU2
 NRG-Indian River Power

	Task 1 Site Prep., Veg. Clear, and E&S Controls			Task 2 Grading and Construct Cover		Task 3 Restoration		Totals		
	HRS	COST		HRS	COST	HRS	COST	HRS	COST	
OFFICE SUPPORT										
Admin. Support		\$49			\$196		\$196		\$784	
PMA		\$73			\$219		\$73		\$438	
Project Eng / Sci		\$79			\$474		\$474		\$1,896	
Senior Project Eng /Sci		\$122			\$488		\$488		\$1,952	
PM / CPM		\$153			\$459		\$306		\$1,530	
TOTAL OFFICE SUPPORT					\$2,142		\$2,921		\$1,537	
									\$6,600	
FIELD LABOR										
Laborer		\$73 2 laborers full-time			\$33,580		\$18,980		\$65,700	
Foreman		\$89 full-time blue card			\$20,470		\$11,570		\$40,050	
Construction Manager		\$99 gold card / CCR			\$22,770		\$12,870		\$44,550	
TOTAL FIELD LABOR					\$76,820		\$43,420		\$150,300	
EXPENSES (2)										
			UNITS	COST	UNITS	COST	UNITS	COST	UNITS	COST
Loader with operator	\$1,050 per day		18	\$18,900	13	\$13,650	0	\$0	31	\$32,550
Dump truck with driver	\$800 per day		0	\$0	13	\$10,400	0	\$0	13	\$10,400
Excavator with operator	\$1,500 per day		0	\$0	13	\$19,500	0	\$0	13	\$19,500
Dozer with operator	\$1,500 per day		18	\$27,000	13	\$19,500	0	\$0	31	\$46,500
Water truck with operator	\$800 per day		23	\$18,400	13	\$10,400	0	\$0	36	\$28,800
Temporary Facilities	\$500 per month		2	\$1,000	1	\$500	1	\$500	4	\$2,000
Sub1 - lab (soil suite)	\$450 per sample		0	\$0	2	\$900	0	\$0	2	\$900
Sub - Equip. mod/demob	\$500 per piece		3	\$1,500	2	\$1,000	0	\$0	5	\$2,500
Sub2 - Vegetation clear/grub	\$2,500 per acre		2.3	\$5,625	0	\$0	0	\$0	2	\$5,625
Sub2 - Vegetation removal offsite	\$1,000 per acre		0.0	\$0	0	\$0	0	\$0	0	\$0
Sub3 - loam delivered	\$25 per CY		0	\$0	1,513	\$37,813	0	\$0	1,513	\$37,813
Sub3 - fill delivered	\$16 per CY		2,840	\$45,440	4,538	\$72,600	0	\$0	7,378	\$118,040
Sub3 - hay bales/silt fence	\$8 LF		1,446	\$11,568	0	\$0	0	\$0	1,446	\$11,568
Sub4 - Landscaper (tree/shrub)	\$100 each		0	\$0	0	\$0	210	\$21,000	210	\$21,000
Sub4 - Hydroseeder	\$2,600 per acre		0	\$0	0	\$0	3.0	\$7,800	3	\$7,800
PU Truck	\$58 per day		46	\$2,668	26	\$1,508	18	\$1,044	90	\$5,220
PPE & Misc.	\$25 per day		23	\$575	13	\$325	9	\$225	45	\$1,125
Per diem	\$140 per night		151	\$21,140	117	\$16,380	45	\$6,300	313	\$43,820
Misc. Fee's/materials	\$50 per item		4	\$200	5	\$250	3	\$150	12	\$600
SUBTOTAL EXPENSES				\$154,016		\$204,726		\$37,019		\$395,760
TOTAL				\$232,978		\$251,067		\$68,616		\$552,660

Notes:

1. Subcontractor costs are "pre-budgetary" estimated. Firm quotes will be obtained prior to job initiation.

CAPITAL COST

Feasibility Study Cost Estimate - DETAIL
 S-2: Targeted Soil Cover with Land Use Controls
 Burton Island OU2
 NRG-Indian River Power

Area of Cover ac. from CAD (incl. exposed, steep, and pond banks)

SITE PREP			
area of exposed ash	<input type="text" value="0.75"/> ac.	<input type="text" value="1"/> site kickoff mtg	
area of vegetation removal	<input type="text" value="2.25"/> ac.		
at a rate of	<input type="text" value="1.0"/> ac / day =	<input type="text" value="3"/> veg removal days	
length of silt fence	<input type="text" value="1,446"/> ft for work areas		
at a rate of	<input type="text" value="1,600"/> ft / day =	<input type="text" value="1"/> silt fence install days	
existing access roads	<input type="text" value="12,200"/> ft	from CAD for perimeter road	
% exist. rd. needs improvement	<input type="text" value="30"/> %		
	<input type="text" value="200"/> ft of new roads per ac of cover		
new access roads (build)	<input type="text" value="600"/> ft		
average road work rate	<input type="text" value="250"/> ft/day =	<input type="text" value="18"/> access road days	
	<input type="text" value="1"/> tons road fill per ft of road		
	<input type="text" value="4,260"/> tons road fill		
	<input type="text" value="2,840"/> cy road fill at	<input type="text" value="1.5"/> tons road fill per cy	
<i>subtotal site prep</i>			<input type="text" value="23"/> days

GRADING	
days to grade cover areas	<input type="text" value="3"/> days at rate of <input type="text" value="1"/> ac / day

COVER			
		<i>COVER THICKNESS:</i> <input type="text" value="12"/> inches compacted	
Loam volume	<input type="text" value="32,670"/> ft ³ compact	loam thickness	<input type="text" value="3"/> inches compacted
	<input type="text" value="1,210"/> cy compact		<input type="text" value="25"/> % bulking factor
	<input type="text" value="1,513"/> cy ex situ		<input type="text" value="12"/> cy (ex situ) per dump truck
	<input type="text" value="126"/> trucks		<input type="text" value="1.5"/> ton / cy ex situ
	<input type="text" value="2,269"/> tons ex situ		
Fill Volume	<input type="text" value="98,010"/> ft ³	fill thickness	<input type="text" value="9"/> inches compacted
	<input type="text" value="3,630"/> cy		<input type="text" value="25"/> % bulking factor
	<input type="text" value="4,538"/> cy ex situ		<input type="text" value="12"/> cy (ex situ) per dump truck
	<input type="text" value="378"/> trucks		<input type="text" value="1.5"/> ton / cy
	<input type="text" value="6,806"/> tons		
TOTAL		<input type="text" value="504"/> TRUCKS	
Days to spread and compact soil:		<input type="text" value="10"/> days at rate of <input type="text" value="640"/> cy (ex situ) / day	

RESTORATION			
Hydro seed	<input type="text" value="2"/> days at rate of	<input type="text" value="1.5"/> ac / day	
	new trees/shrubs at 25 ft spacing	<input type="text" value="70"/> trees/shrubs per acre	
Plant trees/shrubs	<input type="text" value="7"/> days at rate of	<input type="text" value="30"/> trees/shrubs per day	
<i>subtotal restoration</i>			<input type="text" value="9"/> days

TOTAL days on site work

Labor Assumptions:	
admin	<input type="text" value="4"/> hr / sub
PMA/billing	<input type="text" value="2"/> hr / month
procure	<input type="text" value="6"/> hr / sub
contracts	<input type="text" value="4"/> hr / sub
PM/CPM	<input type="text" value="4"/> hr / month
laborers	<input type="text" value="10"/> hr / day
foreman	<input type="text" value="10"/> hr / day
field mgr	<input type="text" value="10"/> hr / day
work days	<input type="text" value="21"/> per month

ANALYTICAL	
imported material	<input type="text" value="1"/> sample per <input type="text" value="5000"/> cy from same source

O&M			
COVER INSPECTIONS			
frequency	<input type="text" value="1"/> inspection per month		
staff personnel	<input type="text" value="1"/> labor rate	<input type="text" value="\$55"/> per hr	
company-owned truck	<input type="text" value="1"/> rental rate	<input type="text" value="\$25"/> per day	
inspection time	<input type="text" value="0.5"/> hr per acre		
<i>subtotal inspection</i>			<input type="text" value="\$1,290"/> per year
PERIMETER PATROLS			
frequency	<input type="text" value="1"/> circuit per day		
staff personnel	<input type="text" value="1"/> labor rate	<input type="text" value="\$55"/> per hr	
company-owned truck	<input type="text" value="1"/> rental rate	<input type="text" value="\$25"/> per day	
patrol time	<input type="text" value="1"/> hr per circuit		
<i>subtotal patrols</i>			<input type="text" value="\$29,200"/> per year
COVER REPAIR			
repair	<input type="text" value="100"/> sq.ft.	<input type="text" value="1"/> per year	
	<input type="text" value="1"/> ft depth	<input type="text" value="4"/> cy	
topsoil	<input type="text" value="\$25"/> per cy, delivered		
seed	<input type="text" value="\$5"/> per sq.ft.		
laborer	<input type="text" value="\$73"/> per hr	<input type="text" value="1"/> hr per 100 sq.ft.	
company-owned truck	<input type="text" value="1"/> rental rate	<input type="text" value="\$25"/> per day	
<i>subtotal cover repair</i>			<input type="text" value="\$698"/> per year
INVASIVES MANAGEMENT (first 5 years only)			
herbicide treatment	<input type="text" value="1"/> ac / day		
unit sub cost	<input type="text" value="\$5,000"/> per acre		
	<input type="text" value="1"/> time per year		
<i>subtotal invasives management</i>			<input type="text" value="\$15,000"/> per year
		<i>first 5 years</i>	<i>after 5 years</i>
SUBTOTAL ANNUAL O&M	<input type="text" value="\$46,188"/>	<input type="text" value="\$31,188"/>	
contingency 15%	<input type="text" value="\$6,928"/>	<input type="text" value="\$4,678.20"/>	
PM 8%	<input type="text" value="\$3,695"/>	<input type="text" value="\$2,495.04"/>	
SUBTOTAL ANNUAL O&M	<input type="text" value="\$56,811"/>	<input type="text" value="\$38,361"/>	

Feasibility Study Cost Estimate - PRESENT VALUE CALCULATION
S-2: Targeted Soil Cover with Land Use Controls
Burton Island OU2
NRG-Indian River Power

interest rate		2%	
calendar year	year no.	costs	PV
2012	0		
2013	1	\$56,811	\$55,697
2014	2	\$56,811	\$54,605
2015	3	\$56,811	\$53,535
2016	4	\$56,811	\$52,485
2017	5	\$56,811	\$51,456
2018	6	\$38,361	\$34,064
2019	7	\$38,361	\$33,396
2020	8	\$38,361	\$32,741
2021	9	\$38,361	\$32,099
2022	10	\$38,361	\$31,470
2023	11	\$38,361	\$30,853
2024	12	\$38,361	\$30,248
2025	13	\$38,361	\$29,654
2026	14	\$38,361	\$29,073
2027	15	\$38,361	\$28,503
2028	16	\$38,361	\$27,944
2029	17	\$38,361	\$27,396
2030	18	\$38,361	\$26,859
2031	19	\$38,361	\$26,332
2032	20	\$38,361	\$25,816
2033	21	\$38,361	\$25,310
2034	22	\$38,361	\$24,814
2035	23	\$38,361	\$24,327
2036	24	\$38,361	\$23,850
2037	25	\$38,361	\$23,382
2038	26	\$38,361	\$22,924
2039	27	\$38,361	\$22,474
2040	28	\$38,361	\$22,034
2041	29	\$38,361	\$21,602
2042	30	\$38,361	\$21,178
		TOTAL	TOTAL PV
		\$1,243,087	\$946,119

Feasibility Study Cost Estimate - SUMMARY
S-3: Full Soil Cover with Institutional Controls
Burton Island OU2
NRG-Indian River Power

<i>Task</i>		<i>Capital Cost</i>	<i>O&M Costs</i>
Capital Costs			
Permitting		\$100,000	--
Site Preparation		\$1,903,078	--
Cover Placement		\$7,333,674	--
Restoration		\$1,418,342	--
Universal Environmental Covenant		\$300,000	--
Subtotal:		\$11,055,094	--
Contingency	15%	\$1,658,264	--
Project Management	8%	\$884,408	--
Total Capital Costs:		\$13,597,766	--
Years of Construction		3	--
Discount Rate		2%	--
Total Capital Cost Present Worth (2012 \$)		\$13,071,456	--
Annual O&M Costs			
Cover Inspection		--	\$31,188
Cover Repair		--	\$698
Invasives Management (first 5 years only)		--	\$455,500
Subtotal:		--	\$487,386
Contingency	15%	--	\$73,108
Project Management	8%	--	\$38,991
Total Annual O&M Costs (first 5 years)		--	\$599,485
Total Annual O&M Costs (after 5 years)		--	\$39,220
Years of Operation		--	30
Discount Rate		--	2%
Total O&M Present Worth (2012 \$)		--	\$3,316,193
Total Present Worth Cost (2012 \$, 30 Yrs at 2%)			\$16,387,649

Feasibility Study Cost Estimate - DETAIL
S-3: Full Soil Cover with Institutional Controls
Burton Island OU2
NRG-Indian River Power

	Task 1 Site Prep., Veg. Clear, and E&S Controls		Task 2 Grading and Construct Cover		Task 3 Restoration		Totals			
	HRS	COST	HRS	COST	HRS	COST	HRS	COST		
OFFICE SUPPORT										
Admin. Support		\$49		\$196		\$392		\$784		
PMA		\$73		\$1,387		\$2,701		\$6,059		
Project Eng / Sci		\$79		\$474		\$948		\$1,896		
Senior Project Eng /Sci		\$122		\$488		\$976		\$1,952		
PM / CPM		\$153		\$5,814		\$11,169		\$25,092		
TOTAL OFFICE SUPPORT				\$8,359		\$16,186		\$11,238		
								\$35,783		
FIELD LABOR										
Laborer		\$73 2 laborers full-time	3900	\$284,700	7582	\$553,486	5480	\$400,040	16,962	\$1,238,226
Foreman		\$89 full-time blue card	1950	\$173,550	3791	\$337,399	2740	\$243,860	8,481	\$754,809
Construction Manager		\$99 gold card / CCR	1950	\$193,050	3791	\$375,309	2740	\$271,260	8,481	\$839,619
TOTAL FIELD LABOR				\$651,300		\$1,266,194		\$915,160		\$2,832,654
EXPENSES (2)			UNITS	COST	UNITS	COST	UNITS	COST	UNITS	COST
Loader with operator	\$1,050 per day		98	\$102,900	379	\$398,055	0	\$0	477	\$500,955
Dump truck with driver	\$800 per day		0	\$0	379	\$303,280	0	\$0	379	\$303,280
Excavator with operator	\$1,500 per day		0	\$0	379	\$568,650	0	\$0	379	\$568,650
Dozer with operator	\$1,500 per day		98	\$147,000	379	\$568,650	0	\$0	477	\$715,650
Water truck with operator	\$800 per day		195	\$156,000	379	\$303,280	0	\$0	574	\$459,280
Temporary Facilities	\$500 per month		10	\$5,000	15	\$7,500	14	\$7,000	39	\$19,500
Sub1 - lab (soil suite)	\$450 per sample		0	\$0	37	\$16,650	0	\$0	37	\$16,650
Sub - Equip. mod/demob	\$500 per piece		3	\$1,500	2	\$1,000	0	\$0	5	\$2,500
Sub2 - Vegetation clear/grub	\$2,500 per acre		90	\$225,875	0	\$0	0	\$0	90	\$225,875
Sub2 - Vegetation removal offsite	\$1,000 per acre		90	\$90,350	0	\$0	0	\$0	90	\$90,350
Sub3 - loam delivered	\$25 per CY		0	\$0	45,930	\$1,148,240	0	\$0	45,930	\$1,148,240
Sub3 - fill delivered	\$16 per CY		16,213	\$259,413	137,789	\$2,204,620	0	\$0	154,002	\$2,464,033
Sub3 - hay bales/silt fence	\$8 LF		7,968	\$63,746	0	\$0	0	\$0	7,968	\$63,746
Sub4 - Landscaper (tree/shrub)	\$100 each		0	\$0	0	\$0	175	\$17,500	175	\$17,500
Sub4 - Hydroseeder	\$2,600 per acre		0	\$0	0	\$0	91.1	\$236,860	91	\$236,860
PU Truck	\$58 per day		390	\$22,620	758	\$43,976	548	\$31,784	1,696	\$98,380
PPE & Misc.	\$25 per day		195	\$4,875	379	\$9,478	274	\$6,850	848	\$21,203
Per diem	\$140 per night		1171	\$163,940	3412	\$477,666	1370	\$191,800	5,953	\$833,406
Misc. Fee's/materials	\$50 per item		4	\$200	5	\$250	3	\$150	12	\$600
SUBTOTAL EXPENSES				\$1,243,419		\$6,051,294		\$491,944		\$7,786,657
TOTAL				\$1,903,078		\$7,333,674		\$1,418,342		\$10,655,094

Notes:

1. Subcontractor costs are "pre-budgetary" estimated. Firm quotes will be obtained prior to job initiation.

Feasibility Study Cost Estimate - DETAIL
 S-3: Full Soil Cover with Institutional Controls
 Burton Island OU2
 NRG-Indian River Power

Area of OU2 ac. from CAD (OU2)
 area of covered shoreline slopes ac.
 Area of Full Cover ac.

SITE PREP

area of exposed ash	<input type="text" value="0.75"/> ac.	<input type="text" value="1"/> site kickoff mtg
area of vegetation removal	<input type="text" value="90"/> ac.	
at a rate of	<input type="text" value="1.0"/> ac / day =	<input type="text" value="91"/> veg removal days
length of silt fence	<input type="text" value="7,968"/> ft for work areas	
at a rate of	<input type="text" value="1,600"/> ft / day =	<input type="text" value="5"/> silt fence install days
existing access roads	<input type="text" value="12,200"/> ft	from CAD for perimeter road
% exist. rd. needs improvement	<input type="text" value="50"/> %	
	<input type="text" value="200"/> ft of new roads per ac of cover	
new access roads (build)	<input type="text" value="18,220"/> ft	
average road work rate	<input type="text" value="250"/> ft/day =	<input type="text" value="98"/> access road days
	<input type="text" value="1"/> tons road fill per ft of road	
	<input type="text" value="24,320"/> tons road fill	
	<input type="text" value="16,213"/> cy road fill at	<input type="text" value="1.5"/> tons road fill per cy
subtotal site prep		<input type="text" value="195"/> days

GRADING

days to grade cover areas days at rate of ac / day

COVER

COVER THICKNESS: inches compacted

Loam volume	<input type="text" value="992,079"/> ft3 compact	loam thickness	<input type="text" value="3"/> inches compacted
	<input type="text" value="36,744"/> cy compact		<input type="text" value="25"/> %, bulking factor
	<input type="text" value="45,930"/> cy ex situ		<input type="text" value="12"/> cy (ex situ) per dump truck
	<input type="text" value="3,827"/> trucks		<input type="text" value="1.5"/> ton / cy ex situ
	<input type="text" value="68,894"/> tons ex situ		
Fill Volume	<input type="text" value="2,976,237"/> ft3	fill thickness	<input type="text" value="9"/> inches compacted
	<input type="text" value="110,231"/> cy		<input type="text" value="25"/> %, bulking factor
	<input type="text" value="137,789"/> cy ex situ		<input type="text" value="12"/> cy (ex situ) per dump truck
	<input type="text" value="11,482"/> trucks		<input type="text" value="1.5"/> ton / cy
	<input type="text" value="206,683"/> tons		
TOTAL	<input type="text" value="15,310"/> TRUCKS		
Days to spread and compact soil:	<input type="text" value="288"/> days at rate of	<input type="text" value="640"/> cy (ex situ) / day	

RESTORATION

Hydro seed	<input type="text" value="61"/> days at rate of	<input type="text" value="1.5"/> ac / day
new trees/shrubs at 25 ft spacing	<input type="text" value="213"/> days at rate of	<input type="text" value="70"/> trees/shrubs per acre
Plant trees/shrubs	<input type="text" value="213"/> days at rate of	<input type="text" value="30"/> trees/shrubs per day
subtotal restoration	<input type="text" value="274"/> days	

TOTAL days on site work

Labor Assumptions:

admin	<input type="text" value="4"/> hr / sub
PMA/billing	<input type="text" value="2"/> hr / month
procure	<input type="text" value="6"/> hr / sub
contracts	<input type="text" value="4"/> hr / sub
PM/CPM	<input type="text" value="4"/> hr / month
laborers	<input type="text" value="10"/> hr / day
foreman	<input type="text" value="10"/> hr / day
field mgr	<input type="text" value="10"/> hr / day
work days	<input type="text" value="21"/> per month

ANALYTICAL

imported material sample per cy from same source

O&M

COVER INSPECTIONS

frequency	<input type="text" value="1"/> inspection per month
staff personnel	<input type="text" value="1"/> labor rate <input type="text" value="\$55"/> per hr
company-owned truck	<input type="text" value="1"/> rental rate <input type="text" value="\$25"/> per day
inspection time	<input type="text" value="0.5"/> hr per acre
subtotal inspection	<input type="text" value="\$31,188"/> per year

COVER REPAIR

repair	<input type="text" value="100"/> sq.ft.	<input type="text" value="1"/> per year
	<input type="text" value="1"/> ft depth	<input type="text" value="4"/> cy
topsoil	<input type="text" value="\$25"/> per cy, delivered	
seed	<input type="text" value="\$5"/> per sq.ft.	
laborer	<input type="text" value="\$73"/> per hr	<input type="text" value="1"/> hr per 100 sq.ft.
company-owned truck	<input type="text" value="1"/> rental rate	<input type="text" value="\$25"/> per day
subtotal cover repair	<input type="text" value="\$698"/> per year	

INVASIVES MANAGEMENT (first 5 years only)

herbicide treatment	<input type="text" value="1"/> ac / day
unit sub cost	<input type="text" value="\$5,000"/> per acre
	<input type="text" value="1"/> time per year
subtotal invasives management	<input type="text" value="\$455,500"/> per year

	<i>first 5 years of O&M</i>	<i>after 5 years of O&M</i>
SUBTOTAL ANNUAL O&M	<input type="text" value="\$487,386"/>	<input type="text" value="\$31,886"/>
contingency	15% <input type="text" value="\$73,108"/>	<input type="text" value="\$4,782.90"/>
PM	8% <input type="text" value="\$38,991"/>	<input type="text" value="\$2,550.88"/>
SUBTOTAL ANNUAL O&M	<input type="text" value="\$599,485"/>	<input type="text" value="\$39,220"/>

Feasibility Study Cost Estimate - PRESENT VALUE CALCULATION
S-3: Full Soil Cover with Institutional Controls
Burton Island OU2
NRG-Indian River Power

interest rate		2%	
calendar year	year no.	costs	PV
2012	0		
2013	1	\$4,532,589	\$4,443,714
2014	2	\$4,532,589	\$4,356,583
2015	3	\$4,532,589	\$4,271,159
2016	4	\$599,485	\$553,831
2017	5	\$599,485	\$542,972
2018	6	\$599,485	\$532,325
2019	7	\$599,485	\$521,888
2020	8	\$599,485	\$511,654
2021	9	\$39,220	\$32,817
2022	10	\$39,220	\$32,174
2023	11	\$39,220	\$31,543
2024	12	\$39,220	\$30,925
2025	13	\$39,220	\$30,318
2026	14	\$39,220	\$29,724
2027	15	\$39,220	\$29,141
2028	16	\$39,220	\$28,569
2029	17	\$39,220	\$28,009
2030	18	\$39,220	\$27,460
2031	19	\$39,220	\$26,922
2032	20	\$39,220	\$26,394
2033	21	\$39,220	\$25,876
2034	22	\$39,220	\$25,369
2035	23	\$39,220	\$24,871
2036	24	\$39,220	\$24,384
2037	25	\$39,220	\$23,906
2038	26	\$39,220	\$23,437
2039	27	\$39,220	\$22,977
2040	28	\$39,220	\$22,527
2041	29	\$39,220	\$22,085
2042	30	\$39,220	\$21,652
2043	31	\$39,220	\$21,228
2044	32	\$39,220	\$20,811
2045	33	\$39,220	\$20,403
		TOTAL	TOTAL PV
		\$17,575,684	\$16,387,649
		TOTAL O&M ONLY	TOTAL PV O&M ONLY
		\$3,977,918	\$3,316,193
		TOTAL CAP ONLY	TOTAL PV CAP ONLY
		\$13,597,766	\$13,071,456

Feasibility Study Cost Estimate - SUMMARY
S-4: Excavation with Off-Site Disposal
Burton Island OU2
NRG-Indian River Power

<i>Task</i>		<i>Capital Cost</i>	<i>O&M Costs</i>
Capital Costs			
Permitting		\$200,000	--
Site Preparation		\$2,482,576	--
Excavation		\$258,236,044	--
Restoration		\$33,317,848	--
Subtotal:		\$294,236,469	--
Contingency	15%	\$44,135,470	--
Project Management	8%	\$23,538,918	--
Total Capital Costs:		\$361,910,857	--
Years of Operation		23	--
Discount Rate		2%	--
Total Capital Cost Present Worth (2012 \$)		\$287,832,490	--
Annual O&M Costs			
Restoration Repair (first 5 years only)		--	\$814
Invasives Management (first 5 years only)		--	\$470,000
Subtotal:		--	\$470,814
Contingency	15%	--	\$70,622
Project Management	8%	--	\$37,665
Total Annual O&M Costs (first 5 years)		--	\$579,101
Years of Operation		--	5
Discount Rate		--	2%
Total O&M Present Worth (2012 \$)		--	\$1,730,972
Total Present Worth Cost (2012 \$, 5 Yrs at 2%)			\$289,563,462

Feasibility Study Cost Estimate - DETAIL
S-4: Excavation and Off-Site Disposal
Burton Island OU2
NRG-Indian River Power

	Task 1 Site Prep., Veg. Clear, and E&S Controls		Task 2 Excavation		Task 3 Restoration		Totals	
	HRS	COST	HRS	COST	HRS	COST	HRS	COST
OFFICE SUPPORT								
Admin. Support \$49	4	\$196	8	\$392	12	\$588	24	\$1,176
PMA \$73	22	\$1,606	511	\$37,303	168	\$12,264	701	\$51,173
Project Eng / Sci \$79	6	\$474	12	\$948	18	\$1,422	36	\$2,844
Senior Project Eng /Sci \$122	4	\$488	8	\$976	12	\$1,464	24	\$2,928
PM / CPM \$153	43	\$6,579	1,022	\$156,366	336	\$51,408	1,401	\$214,353
TOTAL OFFICE SUPPORT		\$9,343		\$195,985		\$67,146		\$272,474
FIELD LABOR								
Laborer \$73 2 laborers full-time	4,480	\$327,040	107,257	\$7,829,743	35,280	\$2,575,440	147,017	\$10,732,223
Foreman \$89 full-time blue card	2,240	\$199,360	53,628	\$4,772,925	17,640	\$1,569,960	73,508	\$6,542,245
Construction Manager \$99 gold card / CCR	2,240	\$221,760	53,628	\$5,309,209	17,640	\$1,746,360	73,508	\$7,277,329
TOTAL FIELD LABOR		\$748,160		\$17,911,877		\$5,891,760		\$24,551,797
EXPENSES (2)	UNITS	COST	UNITS	COST	UNITS	COST	UNITS	COST
Loader with operator \$22,050 per month	11	\$242,550	256	\$5,644,800	71	\$1,565,550	338	\$7,452,900
Dump truck with driver \$16,800 per month	0	\$0	256	\$4,300,800	71	\$1,192,800	327	\$5,493,600
Excavator with operator \$31,500 per month	0	\$0	256	\$8,064,000	71	\$2,236,500	327	\$10,300,500
Dozer with operator \$31,500 per month	11	\$346,500	256	\$8,064,000	71	\$2,236,500	338	\$10,647,000
Water truck with operator \$16,800 per month	11	\$184,800	256	\$4,300,800	71	\$1,192,800	338	\$5,678,400
Temporary Facilities \$500 per month	11	\$5,500	256	\$128,000	84	\$42,000	351	\$175,500
Sub1 - lab (soil suite) \$450 per sample	0	\$0	487	\$219,150	190	\$85,500	677	\$304,650
Sub - Equip. mod/demob \$500 per piece	3	\$1,500	2	\$1,000	0	\$0	5	\$2,500
Sub2 - Vegetation clear/grub \$2,500 per acre	93	\$232,500	0	\$0	0	\$0	93	\$232,500
Sub2 - Vegetation removal offsite \$1,000 per acre	93	\$93,000	0	\$0	0	\$0	93	\$93,000
Sub3 - loam delivered \$25 per CY	0	\$0	0	\$0	47,392	\$1,184,792	47,392	\$1,184,792
Sub3 - fill delivered \$16 per CY	20,667	\$330,667	0	\$0	900,442	\$14,407,067	921,108	\$14,737,733
Sub3 - hay bales/silt fence \$8 LF	8,094	\$64,753	0	\$0	0	\$0	8,094	\$64,753
Sub4 - Landscaper (tree/shrub) \$100 each	0	\$0	0	\$0	6,580	\$658,000	6,580	\$658,000
Sub4 - Hydroseeder \$2,600 per acre	0	\$0	0	\$0	94	\$244,400	94	\$244,400
Dewatering and Treatment \$1.30 per CY	0	\$0	1,000,000	\$1,300,000	0	\$0	1,000,000	\$1,300,000
T&D (non-haz) \$55 per ton	0	\$0	3,647,128	\$200,592,047	0	\$0	3,647,128	\$200,592,047
PU Truck \$58 per day	448	\$25,984	10,726	\$622,089	3,528	\$204,624	14,702	\$852,697
PPE & Misc. \$25 per day	224	\$5,600	5,363	\$134,071	1,764	\$44,100	7,351	\$183,771
Per diem \$140 per night	1,368	\$191,520	48,266	\$6,757,175	14,744	\$2,064,160	64,378	\$9,012,855
Misc. Fee's/materials \$50 per item	4	\$200	5	\$250	3	\$150	12	\$600
SUBTOTAL EXPENSES		\$1,725,073		\$240,128,182		\$27,358,942		\$269,212,198
TOTAL		\$2,482,576		\$258,236,044		\$33,317,848		\$294,036,469

Notes:

1. Subcontractor costs are "pre-budgetary" estimated. Firm quotes will be obtained prior to job initiation.

Feasibility Study Cost Estimate - DETAIL
 S-4: Excavation and Off-Site Disposal
 Burton Island OU2
 NRG-Indian River Power

Area of Excavation ac. from CAD (OU2)

SITE PREP			
area of exposed ash	<input type="text" value="1"/>	ac.	<input type="text" value="1"/> site kickoff mtg
area of vegetation removal	<input type="text" value="93"/>	ac.	
at a rate of	<input type="text" value="1.0"/>	ac / day =	<input type="text" value="93"/> veg removal days
length of silt fence	<input type="text" value="8,094"/>	ft for work areas	
at a rate of	<input type="text" value="1,600"/>	ft / day =	<input type="text" value="6"/> silt fence install days
existing access roads	<input type="text" value="12,200"/>	ft	from CAD for perimeter road
% exist. rd. needs improvement	<input type="text" value="100"/>	%	
	<input type="text" value="200"/>	ft of new roads per ac of excavation	
new access roads (build)	<input type="text" value="18,800"/>	ft	
average road work rate	<input type="text" value="250"/>	ft/day =	<input type="text" value="124"/> access road days
	<input type="text" value="1"/>	tons road fill per ft of road	
	<input type="text" value="31,000"/>	tons road fill	
	<input type="text" value="20,667"/>	cy road fill at	<input type="text" value="1.5"/> tons road fill per cy
<i>subtotal site prep</i> <input type="text" value="224"/> days			

Labor Assumptions:	
admin	<input type="text" value="4"/> hr / sub
PMA/billing	<input type="text" value="2"/> hr / month
procure	<input type="text" value="6"/> hr / sub
contracts	<input type="text" value="4"/> hr / sub
PM/CPM	<input type="text" value="4"/> hr / month
laborers	<input type="text" value="10"/> hr / day
foreman	<input type="text" value="10"/> hr / day
field mgr	<input type="text" value="10"/> hr / day
work days	<input type="text" value="21"/> per month

ANALYTICAL			
imported material	<input type="text" value="1"/> sample per	<input type="text" value="5000"/> cy	from same source
excavated material	<input type="text" value="1"/> sample per	<input type="text" value="1000"/> cy	

O&M			
INVASIVES MANAGEMENT (first 5 years only)			
herbicide treatment	<input type="text" value="1"/> ac / day		
unit sub cost	<input type="text" value="\$5,000"/>		per acre
	<input type="text" value="1"/>		time per year
<i>subtotal invasives management</i>		<input type="text" value="\$470,000"/>	per year
RESTORATION REPAIR (first 5 years only)			
initial restoration	<input type="text" value="\$33,317,848"/>		
initial restoration area	<input type="text" value="94"/>	ac.	
initial restoration unit cost	<input type="text" value="\$354,445"/>	per acre	
repair	<input type="text" value="100"/>	sq.ft.	<input type="text" value="1"/> per year
<i>subtotal repair</i>		<input type="text" value="\$814"/>	per year
<i>first 5 years</i>			
SUBTOTAL ANNUAL O&M		<input type="text" value="\$470,814"/>	
contingency	15%	<input type="text" value="\$70,622"/>	
PM	8%	<input type="text" value="\$37,665"/>	
SUBTOTAL ANNUAL O&M		<input type="text" value="\$579,101"/>	

Excavation Quantity and Rate Assumptions			
see CAD calc for in situ volume estimate backup			
low range	<input type="text" value="1,903,208"/>	cy in situ	based on fixed 'bottom' depth at MLW elevation (0).
high range	<input type="text" value="1,987,062"/>	cy in situ	based on variable 'bottom' depth of FE soil borings.
Bulking factor for excavation (wet or dry): 1 cy soil in situ = <input type="text" value="1.25"/> cy soil ex situ			
low range	<input type="text" value="2,379,010"/>	cy ex situ	
high range	<input type="text" value="2,483,828"/>	cy ex situ	
Dump truck estimate: avg. capacity dump truck <input type="text" value="12"/> cy soil ex situ			
low range	<input type="text" value="198,251"/>	trucks	
high range	<input type="text" value="206,986"/>	trucks	
Material weight conversion: 1 cy ex situ soil weighs <input type="text" value="1.5"/> tons			
low range	<input type="text" value="3,568,515"/>	tons	
high range	<input type="text" value="3,725,741"/>	tons	
WET vs. DRY material <input type="text" value="1,000,000"/> cy in situ WET based on groundwater/tidal study results, approx. bottom 7 ft wet.			
low range	<input type="text" value="903,208"/>	cy in situ DRY	<input type="text" value="1,129,010"/> cy ex situ DRY
high range	<input type="text" value="987,062"/>	cy in situ DRY	<input type="text" value="1,233,828"/> cy ex situ DRY
Production rate (DRY) T&D =	<input type="text" value="500"/>	cy/day	
Production rate (WET) T&D =	<input type="text" value="333"/>	cy/day	
Project duration T&D =	low	<input type="text" value="5,258"/> days	high <input type="text" value="5,468"/> days
		<input type="text" value="250"/> months	<input type="text" value="260"/> months
		<input type="text" value="21"/> years	<input type="text" value="22"/> years

LAND RESTORATION		VEGETATIVE RESTORATION	
area for restoration	<input type="text" value="94"/> ac	Hydro seed	<input type="text" value="63"/> days at rate of <input type="text" value="1.5"/> ac / day
target elevation	<input type="text" value="5"/> ft above MLW (assuming bottom of excavation is at MLW)	new trees/shrubs at 25 ft spacing	<input type="text" value="70"/> trees/shrubs per acre
topsoil	<input type="text" value="3"/> inches	fill	<input type="text" value="4.75"/> ft
topsoil	<input type="text" value="37,913"/> cy compacted	fill	<input type="text" value="720,353"/> cy compacted
1 cy soil in situ =	<input type="text" value="1.25"/> cy soil ex situ	Plant trees/shrubs	<input type="text" value="220"/> days at rate of <input type="text" value="30"/> trees/shrubs per day
	<input type="text" value="47,392"/> cy of topsoil to import	<i>subtotal veg restoration</i> <input type="text" value="283"/> days	
Days to spread and compact soil:	<input type="text" value="1,481"/> days at rate of <input type="text" value="640"/> cy (ex situ) / day		

TOTAL days on site work

Feasibility Study Cost Estimate - PRESENT VALUE CALCULATION
S-4: Excavation with Off-Site Disposal
Burton Island OU2
NRG-Indian River Power

interest rate		2%	
calendar year	year no.	costs	PV
2012	0		
2013	1	\$15,735,255	\$15,426,720
2014	2	\$15,735,255	\$15,124,236
2015	3	\$15,735,255	\$14,827,682
2016	4	\$15,735,255	\$14,536,943
2017	5	\$15,735,255	\$14,251,905
2018	6	\$15,735,255	\$13,972,456
2019	7	\$15,735,255	\$13,698,486
2020	8	\$15,735,255	\$13,429,888
2021	9	\$15,735,255	\$13,166,557
2022	10	\$15,735,255	\$12,908,389
2023	11	\$15,735,255	\$12,655,284
2024	12	\$15,735,255	\$12,407,141
2025	13	\$15,735,255	\$12,163,864
2026	14	\$15,735,255	\$11,925,357
2027	15	\$15,735,255	\$11,691,526
2028	16	\$15,735,255	\$11,462,280
2029	17	\$15,735,255	\$11,237,530
2030	18	\$15,735,255	\$11,017,186
2031	19	\$15,735,255	\$10,801,163
2032	20	\$15,735,255	\$10,589,375
2033	21	\$15,735,255	\$10,381,740
2034	22	\$15,735,255	\$10,178,177
2035	23	\$15,735,255	\$9,978,605
2036	24	\$579,101	\$360,039
2037	25	\$579,101	\$352,980
2038	26	\$579,101	\$346,059
2039	27	\$579,101	\$339,273
2040	28	\$579,101	\$332,621
2041	29	\$0	\$0
2042	30	\$0	\$0
		TOTAL	TOTAL PV
		\$364,806,361	\$289,563,462
		TOTAL O&M ONLY	TOTAL PV O&M ONLY
		\$2,895,504	\$1,730,972
		TOTAL CAP ONLY	TOTAL PV CAP ONLY
		\$361,910,857	\$287,832,490