

Delaware Weatherization Assistance Program Price List
October 15, 2011

		Client Name:				Contractor:	
Local agency logo/name		Address:				Submission Date:	
						Reference Number:	
Health and Safety	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Heating Tune-Up:	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Reconnect ductwork	\$35.00	Per Joint or 3' Section		\$ -			\$35.00
Replace Ductwork	\$25.00	per 2" section		\$ -	Work on return ducts is H&S cost		
Mastic return ductwork	\$2.50	Per Joint		\$ -	Work on return ducts is H&S cost	\$0.50	\$2.00
Digital thermostat	\$85.00	EA		\$ -		\$50.00	\$35.00
Clean and Tune heating unit	\$110.00	Per Hour		\$ -	Per Man hour - 3 Hour maximum		
Other Health & Safety	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Install roof vent	\$70.00	EA		\$ -		\$20.00	\$50.00
Install soffit vent	\$38.00	EA		\$ -		\$3.00	\$35.00
Install baffle	\$8.00	EA		\$ -		\$3.00	\$5.00
Tunnel Around Knob and Tube (in attic)	\$4.00	LF		\$ -	With 1" Ridgid Foamboard Maintaining a 3" Air Gap	\$1.00	\$3.00
Install junction box	\$50.00	EA		\$ -	Clamshell is Suitable	\$15.00	\$35.00
Replace bath fan and vent (hardpipe) outside	\$300.00	EA		\$ -	Insulate Pipe w/ Ductwrap. Energy Star fan required	\$105.00	\$195.00
Make up air vent (2-4 " round)	\$4.00	LF		\$ -			
Vent existing bath fan to roof (hardpipe & roof vent)	\$180.00	EA		\$ -	Insulate Pipe w/ Ductwrap	\$40.00	\$140.00
Install Temperature and Pressure Relief Valve	\$50.00	EA		\$ -		\$15.00	\$35.00
Install TPR extension tube	\$35.00	EA		\$ -		\$10.00	\$25.00
Install CO detector	\$20.00	EA		\$ -			
Install smoke detector	\$20.00	EA		\$ -			
Install smoke detector, CO detector combo	\$30.00	EA		\$ -			
Install Vapor Barrier in crawl space	\$1.10	Sq . Ft.		\$ -			
General Heat Waste	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Weatherstrip door (install Door Kit, includes door sweep)	\$75.00	complete kit		\$ -		\$25.00	\$50.00
Mastic Supply ductwork	\$2.50	per joint		\$ -		\$0.50	\$2.00
Install door sweep	\$28.00	EA		\$ -		\$11.00	\$17.00
Install sash lock	\$15.50	EA		\$ -		\$3.50	\$12.00
Window repair	\$83.00	Per Hour		\$ -	Per Man hour		
Door repair	\$83.00	Per Hour		\$ -	Per Man hour		
Seal window A/C unit	\$62.00	EA		\$ -	3/4" Insulation, Plywood, and Caulk	\$10.00	\$52.00
Seal basement window	\$42.00	EA		\$ -	3/4" Treated Plywood, Caulk	\$7.00	\$35.00
Box in pull down stairs	\$190.00	EA		\$ -	Plywood, 2" Foamboard & Weatherstrip	\$36.00	\$154.00
Box in can lights	\$50.00	EA		\$ -	15"x16" 24"	\$5.00	\$45.00
Seal crawl vent	\$22.50	EA		\$ -		\$5.00	\$17.50
Air Sealing	\$83.00	Per Hour		\$ -	Per Man hour (10 hour Max charge)		
Install lockset	\$58.00	EA		\$ -		\$35.00	\$23.00
Adjust strike plate	\$12.00	EA		\$ -			\$12.00
Install door strike	\$15.00	EA		\$ -		\$3.00	\$12.00
Water Heater System Treatment:	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Water heater (Elec, Gas, Propane)	\$110.00	EA		\$ -	Per Water Heater - materials paid at invoice costs		\$110.00
Install water heater blanket	\$55.00	EA		\$ -	Tape seams, use zip ties to secure	\$20.00	\$35.00
Water Pipe Insulation	\$2.00	LF		\$ -		\$0.33	\$1.67

Receipts/proof of material costs must be submitted with contractor invoices. Contractor will be paid the price above, regardless of purchase price. Any deviation shall be approved by the local agency and DNREC.

**Delaware Weatherization Assistance Program Price List
October 15, 2011**

Attic hatches	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Insulate access lid, ws, caulk	\$28.33	EA		\$ -	R-38 Fiberglass Batt	\$5.00	\$23.33
Insulate walk-up attic door	\$120.00	EA		\$ -		\$50.00	\$70.00
Cut in, trim attic hatch	\$62.50	EA		\$ -		\$10.00	\$52.50
Insulate Un-insulated Walls to R-15	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Cellulose dense pack	\$2.20	SF of Wall		\$ -		\$0.70	\$1.50
Fiberglass dense pack	\$2.10	SF of Wall		\$ -		\$0.60	\$1.50
R&R aluminum/wood siding 1st story	\$0.25	LF		\$ -	Remove and Reinstall		
R&R aluminum/wood siding 2nd story	\$0.25	LF		\$ -	Remove and Reinstall		
Lead safe work practices inside	\$2.75	SF		\$ -			
Lead safe work practices outside	\$1.75	LF		\$ -			
Uninsulate Ceilings With R-0 To R-38	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Fiberglass, batt, rolled--Attic (R0-R38)	\$1.90	SF		\$ -		\$0.80	\$1.10
Cellose open blow - Attic (R19) 6"	\$1.20	SF		\$ -		\$0.30	\$0.90
Fiberglass, open blow --Attic (R19) 8"	\$1.35	SF		\$ -		\$0.45	\$0.90
Cellose open blow - Attic (R38)	\$1.90	SF		\$ -		\$0.60	\$1.30
Fiberglass, open blow --Attic (R38) 16"	\$2.20	SF		\$ -		\$0.90	\$1.30
Insulation at other depths is pro-rated per above							
Uninsulated Floors With R-0 to R-19	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Fiberglass batt rolled	\$1.60	SF		\$ -		\$0.60	\$1.00
Cellulose dense pack under attic floor	\$3.06	SF		\$ -	8" Joists R-29	\$1.06	\$2.00
Fiberglass dense pack under attic floor	\$3.20	SF		\$ -	8" Joists R-24	\$1.20	\$2.00
Insulate Box Sills To R-19	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Insulate band joist w/ 2 part foam: 1.5" depth	\$3.00	LF		\$ -	R-10	\$1.80	\$1.20
Insulate Foundation	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Insulate crawl door, ws	\$36.00	EA		\$ -			
Other: Necessary Repairs	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Install CFL lightbulb	\$4.00	EA		\$ -			
Install dryer vent: rigid	\$5.50	LF		\$ -	Includes vent cap on outside	\$2.00	\$3.50
Install vent for combustion air	\$48.00	EA		\$ -	Note grill, Mechanical (fan), or Pipe (\$150 fan)		
Patch roof	\$12.00	SF		\$ -			
Build dam around attic access	\$58.50	EA		\$ -		\$6.00	\$52.50
Install chimney cap/birdscreen	\$100.00	EA		\$ -		\$30.00	\$70.00
Install door sill/threshold	\$60.00	EA		\$ -		\$20.00	\$40.00
Install drywall	\$50.00	EA 4'x8' Board		\$ -		\$8.00	\$42.00
Caulking	\$0.57	In ft		\$ -			
Glazing	\$1.37	In ft		\$ -			
Window replacement (Double sash, Low E, Vinyl)	\$3.80	Per Inch		\$ -		\$1.50	\$2.30
Door replacement (metal)	\$590.00	Per Door		\$ -		\$240.00	\$350.00
Door replacement (wood)	\$680.00	Per Door		\$ -		\$300.00	\$380.00
				\$ -			

Receipts/proof of material costs must be submitted with contractor invoices. Contractor will be paid the price above, regardless of purchase price. Any deviation shall be approved by the local agency and DNREC.

Delaware Weatherization Assistance Program Price List
October 15, 2011

				\$ -			
				\$ -			
NID	\$1.00					at cost + handling (3%)	\$83.00/hour
Mobile Home Specific	Cost	# or Unit	Quantity	Total Charge	Notes	Materials	Labor
Fiberglass densepack - roof	\$3.60	SQ FT		\$ -		\$1.20	\$2.40
Fiberglass densepack - belly	\$2.25	SQ FT		\$ -		\$0.90	\$1.35
Belly Board or Membrane repair/replace	\$1.50	SQ FT		\$ -			
Window replacement (mobile home, LO-E slider)	\$4.00	Per United Inch		\$ -		\$1.50	\$2.50
Reflective Roof coating	\$1.90	SQ FT		\$ -		\$0.70	\$1.20
Mastic Duct Boots	\$20.00	per boot		\$ -			
Drip cap (MH)	\$44.00	EA		\$ -		\$9.00	\$35.00
Mobile Home ground moisture barrier	\$0.65	SQ FT		\$ -			
Total				\$ -			
Unless otherwise noted, activities for stick homes and mobile homes are priced the same (ie. Air sealing is \$83.00 per hour for each).							
ENERGY AUDIT/FINAL INSPECTION			Quantity	Total Charge	Labor		Grand Total
Energy Audit				\$ -	\$475.00		\$ -
File review and inspection of previous work				\$ -	\$100.00		
Final Inspection				\$ -	\$250.00		
Re-inspection fee following re-work, per visit				\$ -	\$100.00		
re-inspection including a blower door test or CAZ test				\$ -	\$150.00		
Re-inspection requiring a blower door and CAZ test				\$ -	\$175.00		
Deferral (fee allowed when auditor defers home at walk thru)				\$ -	\$100.00		
Special Notes							