

11.0 Post Construction BMPs Standards and Specifications

11.6 Restoration Practices

11.6.1 Restoration Practices include Regenerative Stormwater Conveyance Systems (RSCS), also known as Coastal Plain Outfalls, and other practices that restore existing degraded natural systems to their former functional condition. Streambank stabilization is also included as a Restoration Practice.

11.6.2 Design variants for Restoration Practices include:

11.6.2.1 Step Pool RSCS

11.6.2.2 Seepage Wetland RSCS

11.6.2.3 Streambank Stabilization

11.6.3 Runoff reduction and pollutant reduction performance credits for Restoration Practices shall be determined by the Department on a case-by-case basis.

11.6.4 Upon facility completion, the owner shall submit post construction verification documents to demonstrate that the restoration practice has been constructed within allowable tolerances in accordance with the approved Sediment and Stormwater Management Plan and accepted by the approving agency.