

Technical Document Updates

March 2013

Article 1

- No changes

Article 2

- 2.01 Delegated Agencies
 - Owner's monitoring requirements reference Section 9.1.02 Monitoring
- 2.02 Plan Policies and Procedures
 - Grandfathering – 12 months to 18 months
 - Sunsetting – allow six years from effective date to begin construction under previous regulations
- 2.04 Offset Provisions rewritten
- 2.04.1 – new offset procedure flow chart
- 2.04.3 – Fee-in-lieu example updated to reflect adjusted numbers

Article 3

- 3.02.1.1 SAS Checklist
 - A. Documents
 - Updated DeIDOT Maintenance contact phone numbers
 - Removed letter from DeIDOT Subdivision based on Traffic Generation Diagram review
 - Updated links for On-Line Background Information
- 3.02.1.2 Project Application Meeting Discussion and Agreement Items
 - Discussion Items
 - Removed TMDL pollutant reduction requirements
 - Removed recharge classification
 - Proposed grading plan – increased size from 10 to 20 acres when requiring engineered control practices
 - Agreement Items
 - Stormwater quality management – Green Technology BMPs revised to runoff reduction BMPs; all items in list edited
 - Stormwater quantity management – updated to reflect Cv and Fv requirements; all items in list edited
 - SAR - Mitigation under consideration – included offset option

Technical Document Updates

- 3.02.1.5 Example Project Application Package
 - Disclaimer added: May contain references to earlier draft versions of documents in some cases, though general process and procedures are unaffected.
- 3.02.1.3 Stormwater Assessment Report
 - Mitigation under consideration for “significant” ratings – included offset option
- 3.02.2.1 Preliminary S&S Plan Review Checklist
 - Stormwater Management Report, item 26.c.ii., changed “2007” to “latest” for site aerial and Land Use Land Cover mapping
- 3.04 Post Construction Stormwater Management
 - For redevelopment, the R_{Pv} shall be reduced to an equivalent 70% of the existing effective imperviousness.
 - Revised references to Green Technology BMPs
 - Proprietary practices now reference Post Construction Stormwater BMP Standards and Specs rather than table of approved practices.
- 3.04.4 DURMMv2 Spreadsheet
 - Updated to better handle upstream areas within the LOD as well as various minor bug fixes
- 3.04.5 DURMMv2 Quick Start Guide
 - Disclaimer added: This Quick-Start Guide was created for an earlier version of DURMMv2. Although some of the screen shots do not exactly match the latest version, the procedures remain the same.
- 3.06.1 Delaware Erosion and Sediment Control Handbook
 - Revised netting specification for erosion control mattings based on comments received
- 3.06.2 Post Construction Stormwater BMP Standards & Specifications
 - Edits to all Post Construction Stormwater BMPs Standards and Specifications and appendices to address public comments received and comments supplied by Center for Watershed Protection. Schematics updated.

Technical Document Updates

Article 4

- 4.01 Construction Review Guidelines
 - Releasing the CCR Review Requirement – section language updated to reference Section 9.1.02 requirements.
- 4.01.2 BMP Construction Checklists – checklists added for:
 - Infiltration
 - Bioretention
 - Vegetated Channels
 - Dry Detention
 - Underground Detention
 - Filtering Systems
 - Wet Pond

Article 5

- 5.01.3 Maintenance Review Checklists – checklists added for:
 - Permeable Pavement
 - Vegetated Roofs
 - Rainwater Harvesting
 - Rooftop Disconnection
 - Vegetated Channels
 - Sheet Flow to Open Space
 - Filtering Systems
 - Constructed Wetlands